CHITALDRUG DIVISION. The 3rd April 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 30th April 1899, for constructing a new Taluk Cutcherry at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1901.

2. The plans and conditions may be seen at the Executive Engineer's office at Chitaldrug

between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for construct-

ing a new Taluk Cutcherry at Davangere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered

cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply. oney on rejected tenders will he-

8. On acceptance of one of the ten	ders, th	e earnest m	oney on re	jected tend	lers will be-
returned.					
Description of work.		,		t of work.	Quantity.
Earthwork excavation		* * *	• • •	C: yds.	1,464
Concrete foundation				C. ft.	5,714
Burnt stone in mortar (foundation)				>>	13,535
Burnt brick in mortar (superstructure)				,,	20,318
Do archwork				~ " ·	291
Stone slabs dressed roughly				S. ft.	1,909
Gothic cornice			* * *	R. ft	169
Cornice 9" deep				22	`806
Perforated parapet wall			***	"	70
China course			* * 4	, ,	364
String course				Sqrs.	13.76
Pointing Plastering with chunam				,,	359.19
Manual and the flooring over concrete	bed noi	ated with cer	$_{ m nent}$	"	62.70-
White-washing and color-washing Ka	dana st	one flagging	with	2)	359.19
White-washing and drossing	T to	00 0		"	14.00
painting and dressing.				C. yd.	72.
Gravel flooring				Sqrs.	62.59
Bamboo matting, outer rid				. "	90.55.
Mangalore tile roofing				, ,,	1.49
Terrace roofing	•••			33	42.92
Bengal terrace roofing	• • •			22.	1.11
Corrugated iron roofing					. 9.44
Teak wood ceiling 1" thick	• • •			$ {No.}$	8-
Zinc gutters, vally				C. ft.	1,066
Teak-wood work				S. ft.	614
Teak-wood pannelled doors		• • •			91
Do battened doors			• • • •	νο̈́.	1
Iron door for Treasury	* * *	* * *			1
Gate for main entrance	 J alasatta		• • •	"	2:
Windows with iron bars with battene	a shubbe	ors	• • • •	S. ft.	724
Do pannelled with glazed shut	ters, iroi	i pars, &c.		No.	24
Cut stone base to wooden pillars					19
Ventilators with iron bars and perfor	ated zin		•••	S. ft.	430
Ventilators, glazed			4 9 6,	No.	4.
Ventilators in front of gables	* * *	***	• • • •	Sqrs.	42.30
Painting	* * *	•••			$9\frac{1}{9}$
Ornamental wooden railings	,	• •	***	R. ft.	ed .
Moulding and complete at entrance	• • • •	• •	* * *	Liui	_ 1
Ornamental finials	• • •	* * *	***	Т	1101
Dais with railing, complete				Lu	mp sum.
Prisoners' dock and witness box, con	aplete				22
Clearing site and levelling ground		,			.17
Fencing and hedging for compound	round T	aluk Cutcher	ry		22
Wood-oiling to wood work	•••	* ***	•••	-212	"
					LADA RAO,
				Execu	tive Engineer